

King Street Cobble


Machine Laid Permeable | Cobble Face




80 MM (3 1/8")




6" x 6"



PATTERNS



Stacked




Running Bond

PALLET SPECIFICATIONS

	Full	Half	Layer
Coverage (ft ²)	105	58.35	11.67
Weight (lbs) (includes pallet weight)	3,618	1,982	396
Layers	9	5	1
Pieces	504	280	56

*Note: This is a special order product and will require a \$500 production fee for any order that is less than 2,000 square feet.

PALLET OVERVIEW



PERMEABILITY

% of Surface Opening: 13%*

Infiltration Rate: > 900 in/hr

*dependent on laying pattern

FINISHES



TRADITIONAL FINISH



TUMBLED FINISH



TABBY FINISH

TRADITIONAL COLORS



BATTERY GRAY



BONFIRE



SWEET GRASS



SHRIMP BOIL

COASTAL COLORS



COLIGNY



NEW SIERRA



CHARLESTON PEARL



JASPER



STORM CLOUD



CANYON

COOL POOL COLORS



WHITE BROWN



WHITE TAN



WHITE CREAM



WHITE GRAY

Lowcountry Paver Products meet & exceed ASTM C 936 requirements.