

King Street Cobble


Machine Laid Permeable | Cobble Face




80 MM (3 1/8")




6" x 6"



PATTERNS



Stacked




Running Bond

PALLET SPECIFICATIONS

	Full	Half	Layer
Coverage (ft ²)	105	58.35	11.67
Weight (lbs) (includes pallet weight)	3,618	1,982	396
Layers	9	5	1
Pieces	504	280	56

*Note: This is a special order product and will require a \$500 production fee for any order that is less than 2,000 square feet.

PALLET OVERVIEW



PERMEABILITY

% of Surface Opening: 13%*

Infiltration Rate: > 900 in/hr

*dependent on laying pattern

FINISHES



TRADITIONAL FINISH



TUMBLED FINISH



TABBY FINISH

TRADITIONAL COLORS



COASTAL COLORS



COOL POOL COLORS

